GOVERNMENT OF TRIPURA
DIRECTORATE OF FIRE & EMERGENCY SERVICES
AGARTALA : TRIPURA

Phone: 0381-232-6451 Email: dg.fire-tr@gov.in website:www.fireservice.tripura.gov.in

No: FSCTFES/2026/00045 **Dated: 04/06/2026**

Sub: FIRE SAFETY CERTIFICATE

Certified that the building or premises as mentioned below have complied with the fire prevention and fire safety requirements in accordance with the conditions laid down in the relevant portions of Part-IV of the latest National Building Code and the Tripura Building Rules and that the building/ premises is fit for occupancy class Educational for a period of 3 (three) year(s) in accordance with renewal from time to time.

Name of the Applicant:-	Gokul Chandra Debnath (Applicant on Behalf)
Name of Owner with Plot details:-	**S. No.** | **Owner Name and Address** 1. | ত্রিপুরা সরকারের পক্ষে শিক্ষা বিভাগ কর্তৃক রক্ষিত
Name of the Property/ Organization/ Commercial establishment	Nayapara English Medium H.S (+2 Stage) School Total covered area of Building / Premises (in Sqm) : 1542.2
Address of the Building/ Premises:-	Area Name Dharmanagar, Ward No.3, Dharmanagar Municipal Council, Post Office Dharmanagar H.O - 799250, North Tripura District, Tripura.

S. No.	Plot No	Total Area (Acre)	Classification
1.	1574	1.1	নাল
2.	1576	0.04	নাল
3.	2812	1.002	নাল
4.	696	0.1	নাল
5.	71	0.075	টিলা

Director,
Fire & Emergency Services,
Or Authorized Signatory
Tripura : Agartala

This certificate will expire on 04/06/2029

Conditions for the Validity of Fire Safety Certificate (NOC).

1. All the fire safety and means of escape facilities shall be maintained in good working conditions at all time. Any lapse rendering fire safety or means of evacuation facilities rendering non-functional shall be the responsibility of the management.

2. There should not be any change of Trade for which this License has been issued.

3. Building sanctioning authority may verify any deviation with regard to the construction/ occupancy in the building. In case of any deviation, the Fire Safety Certificate stands null and void.

4. Water reservoir should always be kept full up to brim.

5. The entrance and exit and the water reservoir should always be free from any obstruction/ projection.

6. The staffs shall be trained for operating fire fighting system and mock evacuation drills be conducted at regular intervals and record be maintained.

NB:- ISSUED

04/06/26

Er. Bual Nath
Grade-1, Consultant Engineer
[Ishaan Building Planning & Designing]
Dharmanagar Municipal Council
Under The Licence Number-43

Digitally signed by TAMAL MAJUMDAR
Date:04-06-2026 17:19:33 PM

GOVERNMENT OF TRIPURA
DIRECTORATE OF FIRE & EMERGENCY SERVICES
AGARTALA : TRIPURA

Phone: 0381-232-6451 Email: dg.fire-tr@gov.in website:www.fireservice.tripura.gov.in

Ref: **FSRTFES/2023/00096** **Dated: 23/02/2026**

To,
Gokul Chandra Debnath
Dharmanagar, North Tripura
Dharmanagar H.O - 799250

Sub: **Fire Safety Recommendation** For Application Reference No **FSRTFES/2023/00096** .

With reference to your Application Reference No FSRTFES/2023/00096 Dated 28/01/2026 Fire Safety Recommendation on fire [illegible] and fire safety measures of the following building/premises is hereby issued in accordance with the conditions laid down in [illegible] pursuant to Part-IV of the latest National Building Code and the Tripura Building Rules.

Name of the Applicant:	Gokul Chandra Debnath
Name of Owner with Plot details:	**S. No.** | **Owner Name and Address**: 1. ত্রিপুরা সরকারের পক্ষে শিক্ষা বিভাগ কর্তৃক রক্ষিত

S. No.	Plot No	Total Area	Classification
1.	1574	1.1	নাল
2.	1576	0.04	নাল
3.	2812	1.002	নাল
4.	696	0.1	নাল
5.	71	0.075	টিলা

Name of the Property/ Organization/ Commercial establishment	Nayapara English Medium H.S (+2 Stage) School
Address of the Building/ Premises:	Area Name Dharmanagar, Ward No.3, Dharmanagar Municipal Council, Post Office Dharmanagar H.O - 799250, North Tripura District, Tripura.

A Fire Safety Certificate (FSC) will be issued, subject to verification of compliance of fire prevention and fire safety measures on which [illegible] and further recommendations enumerated in the attached letter and further submission of application through online system.

14881
Director,
Fire & Emergency Services,
Or Authorized Signatory
Tripura : Agartala

******** *WE SERVE TO SAVE* ********
This certificate shall not be used by the Insurance service provider

Fire Safety Advisory and Suggestion:

1) 1 mitre to be required .
2) 1 mitre to be required .
3) 1 mitre to be required .
4) One No . staircase to be required measuring 1.5 meter as per building plan .
5) One Nos. staircase to be required measuring 1.5 mitre as per building plan .
6) 1.5 mitre to be required.
7) 1.5 mitre to be required .
8) 2 Two Nos. Co2 fire extinguisher capacity of 4.5 kg to be installed in the electric main panel board . 9) 1 (One) No. Co2 fire extinguisher capacity of 2 kg to be installed in the every electric sub - panel board .
10) 1 (One) No. ABC fire extinguisher capacity of 4.5 KG & Co2 fire extinguisher capacity of 2 KG to be installed 1 each interval 15 mitre at ground floor to 1st floor including - 1 to 3. Block.. 11)Office room , Common room , Principal room 2 (Two) Nos. Laboratory room Science Lab 1 (One) No and Store room. ABC fire extinguisher capacity of 4.5 KG to be installed each rooms .
12) 1 (One) No wet chemical extinguisher cap 4.5 kg to be installed in the each kitchen room .
13) 1 (One) No hose reel point system 30 meter long along with accessories such as double door hose box Delivery hose short branch to be installed both G+1 Building (Block - 4&5) in each floor including 1 (One) No landing valve to be provided near at hose reel point.
14) 30 meter long hose reel system to be installed both G+1 Building (Block - 4&5) at each floor connected with down comer system .
15) 4 mm to be installed .
16) Electric main panel to be installed at the ground floor .
17) Manually operated electronic fire alarm system to be installed in the entire building .
18) 1 (One) No Down comer system to be installed in The both G+1 building (Block-4 &5) with m ild steel pipe shall be 100 mm/4 inch dia 4 mm thk.
19) 2 Three) way, inlet valve to be provided both G+1 Building (Block - 4&5) every hose Reel point at each floor.
20) 2 Double door hose box such as delivery hose , short branch to be installed both G+1 Building (Block - 4&5) in each floor .
21) 1 (One) No. point fire inlet to be installed at front side of the both G+1 Building (Block - 4&5) .
22) 2 Double door hose box such as delivery hose , short branch to be installed both G+1 Building (Block - 4&5) in each floor .
23) 1 Terrace level pump minimum 3.5 KG /Cm2 discharge of 450 LPM to be installed both G+1 Building (Block -4&5) with connected terrace level tank .
24) 5 meter head terrace level pump to be provided .
25) Terrace level power supply should be 3 phase .
26) 10,000 litre terrace tank Should be constructed both G+1 Building (Block - 4&5) exclusively for fire fighting purpose .
27) Exit sign should be provided every - floor and every staircase entire the building.
28) Trained person fire fighter should be engage while in emergency .
29) Now fire advisory may be issue in favour of applicant and final inspection would be done after completion of the works for getting final NOC from our end .

23/02/26

Er. Bnas Nath
Grade-1, Consultant Engineer
[Ishaan Building Planning & Designing]
Dharmanagar Municipal Council
Under The Licence Number-43

Digitally signed by MEGHA JAIN
Date: 23-02-2026 18:49:16 PM

23.02.26

(GOKUL CH. DEBNATH)
Principal
Nayapara English Medium H.S. School
Dharmanagar, North Tripura.